

١- قائمة السلع وجدول التسليم

الطليبية المرقمة (١٨ ج / م / س ج ن - ١٨/١) تجهيز وتنصيب منظومة قياس مراقبة الغبار لأفران السمنت (معمل سمنت الكوفة)

| رقم الفقرة | وصف السلع | الكمية | الوحدة | مكان التنصيب النهائي | الموعد المتوقع للتسليم | فترة التجهيز بالأيام | فترة التجهيز المقترح من مقدم العطاء (بمجرد من قبل مقدم العطاء) |
|------------|--|--------|--------|----------------------|---|----------------------|--|
| 1 | <p><u>Supply & Installation complete system of dust monitor for cement kiln as:</u></p> <ul style="list-style-type: none"> - Dust concentration measuring = (mg/m³). - Switchable measuring ranges: (from 0 mg/m³ to 5000 mg/m³). - Sample gas temperature : (0 - 500) C°. - For wet process cement kiln. - Operation voltage (240 VAC , 50Hz). - Insulation class of outdoor unit (IP65). - Ambient temperature : (-10 to 60) C°. - Calibration equipment for both automatic & manual method. - Remote two display with link wireless. - Western origin. - The installation & initial test operation by the supplier company. - Supply spare parts for two years replacement. - Supply document (user manual & maintenance manual). | 1 | | | <p>١- فترة التجهيز بحدود ١٠ يوم تبدأ من تاريخ</p> <p>٢- فترة التنصيب ثلاثون يوماً .</p> | | |
| 2 | Training in Kufa cement plant by expert person from company supplier. | | | | | | |
| 3 | Warranty period: Three (3) months starting from successful test operation. | | | | | | |

Handwritten signatures and initials in the right margin.

Handwritten signature and initials in the right margin.

Handwritten signature and initials in the right margin.

1-list of goods and delivery schedule

Tender NO: (18C/T/SOC - 1 / 2018) Supply & Installation complete system of dust monitor for cement kiln (KUFA CEMENT PLANT)

| Item No. | Goods Description | Quantity | Unit | Final Delivery Destination | Supplying Period (in days) | | |
|----------|--|----------|------|----------------------------|--|---|--|
| | | | | | Estimated Delivery period | The proposed Delivery Period by Bidder (filled by Bidder) | |
| 1 | <p><u>Supply & Installation complete system of dust monitor for cement kiln as:</u></p> <ul style="list-style-type: none"> - Dust concentration measuring = (mg/m³). - Switchable measuring ranges: (from 0 mg/m³ to 5000 mg/m³). - Sample gas temperature : (0 - 500) C°. - For wet process cement kiln. - Operation voltage (240 VAC , 50Hz). - Insulation class of outdoor unit (IP65). - Ambient temperature : (-10 to 60) C°. - Calibration equipment for both automatic & manual method. - Remote two display with link wireless. - Western origin. - The installation & initial test operation by the supplier company. - Supply spare parts for two years replacement. - Supply document (user manual & maintenance manual). | 1 | No | | 1- About (60 Days) starting from: 2- (30 DAYS) For Installations. | | |
| 2 | Training in Kufa cement plant by expert person from company supplier. | | | | | | |
| 3 | Warranty period: Three (3) months starting from successful test operation. | | | | | | |

Handwritten signatures and dates:
 2018/9/3
 2018/9/3
 2018/9/3

Handwritten signatures and dates:
 2018/9/3
 2018/9/3
 2018/9/3

2- Tender: (18 C/T/SOC - 1/2018) Supply & Installation complete system of dust monitor for
 cement kiln
 (KUFA CEMENT PLANT)

| IT.NO | SPECIFICATION | QTY |
|-------|---|-----|
| 1 | <p><u>Supply & Installation complete system of dust monitor for cement kiln as:</u></p> <ul style="list-style-type: none"> - Dust concentration measuring = (mg/m³). - Switchable measuring ranges: (from 0 mg/m³ to 5000 mg/m³). - Sample gas temperature : (0 – 500)C^o. - For wet process cement kiln. - Operation voltage (240 VAC , 50Hz). - Insulation class of outdoor unit (IP65). - Ambient temperature : (-10 to 60) C^o. - Calibration equipment for both automatic & manual method. - Remote two display with link wireless. - Western origin. - The installation & initial test operation by the supplier company. - Supply spare parts for two years replacement. - Supply document (user manual & maintenance manual). | 1 |
| 2 | Training in Kufa cement plant by expert person from company supplier. | |
| 3 | Warranty period: Three (3) months starting from successful test operation. | |

Handwritten signature and date: 2017/4/3

Handwritten signature and date: 2017/4/3

Handwritten signature and date: 2017/4/3

Handwritten signature and date: 2017/4/3

Y- Drawing

| Drawings List | | |
|----------------|-----------------|---------|
| No. Of Drawing | Name Of Drawing | Purpose |
| | لا يوجد | |
| | لا يوجد | |
| | لا يوجد | |
| | لا يوجد | |

Handwritten signature and notes in Arabic script.

Handwritten notes including the number '2014' and other illegible text.

Handwritten signature and notes in Arabic script, including the number '2014'.

Handwritten signature and notes in Arabic script.

ξ- Test And Engineering Inspection

The Following Tests And Engineering Inspection will be executed
(Fill in the schedule of tests and engineering inspections)

| List of Inspections and Tests | |
|-------------------------------|--|
| Line Item No | |
| 1. | Inspection & Test certificate for all items of system . (For kiln produce <u>sulfur resistance cement(SRC)</u>) |
| 2. | Inspection for good finishes for all items. |

Handwritten signatures and notes:

1. *Handwritten signature*

2. *Handwritten signature*

3. *Handwritten signature*

4. *Handwritten signature*

5. *Handwritten signature*